



Far Detector CDR Geometry in MC Simulation

P. Shanahan, R. Hatcher - Fermilab
NOvA Offline Meeting - May 11, 2006

See note 832 for more detail



CDR Geometry



- Changes from previous geometries/simulations for structure and size
 - ▶ Extra thickness of extrusion walls in vertically-oriented planes
 - ▶ Blocks begin and end with vertically-oriented plans
 - ▶ Smaller number of planes
- 1cm-thick expansion gaps between blocks
- Add attempt at upstream cosmic wall
 - ▶ modeled by 18m x 18m x 3 m concrete wall 5m upstream of 1st plane
- FFR file: `cdrc_far.ffr`



Large Scale Validation




- 1000 ν_μ CC events ($\phi \sim 1/E$), with shield

- ▶ Shield shows up at right location, with about right proportion of interactions

- 10000 ν_μ CC events ($\phi \sim 1/E$), no shield

- ▶ Length

- Expect 111.014m
- Observed - 111.006m \pm 0.025m at 90%CL



Width


Expect 15.7m in X and Y

Observe 15.7m within 1mm



Small-scale

- $\sim 22,000$ ν_μ CC events ($\phi \sim 1/E$)
 - ▶ Planes 10-12 only, within 3m radius of detector axis
 - ▶ Use energy hits (not vertices) to illuminate cell structure






Cell Structure



- All Cell Sizes, and Gaps (cell-cell, plane-plane, block-block, extrusion-extrusion) are verified to be correct.
- ▶ Exception: small excess in gap between cells in adjacent vertical extrusions
 - Due to rounding error in CDR table?
 - Not an accumulating effect, so ignorable at least for now



Position of hits - zoomed view



Summary

- CDR geometry changes have been incorporated into GMINOS geometry card file
- Resulting geometry has been validated
- Initial samples have been generated: 100k events each for $\nu_\mu(-\bar{})$ cc, nc, $\nu_e(-\bar{})$ cc.
 - ▶ Data are in /pnfs/p929/newsim/far (gaf and root files)